



NASHOBA REGIONAL SCHOOL DISTRICT

Robert Frieswick, Facilities Director

FACILITIES DEPARTMENT

50 MECHANIC STREET, BOLTON, MA 01740

Office: 978-779-0539 Cell: 978-990-0264

frieswick@nrsd.net

Date: June 24, 2021

Task 1. Removal of Underground Storage Tank (UST)

Addendum #1

The items listed below shall be considered as part of the Contractor's full scope of work and included in the prices given. The Addendum shall be noted on the Contractor's Bid Form.

- 1) Work will need to be completed prior to August 14, 2021.
- 2) Interior pump set, controls, wire, containment to be removed.
- 3) Interior piping to be removed from entry point to elbows going up to boiler room. Pipes are to be vacuumed clean and plugged.
- 4) All piping entries to be sealed with hydraulic cement.
- 5) Pump set electrical and monitoring system to be removed to closest junction box.
- 6) Monitoring system to be removed and disposed of.
- 7) Estimated to be 2000 gallons to be transferred to town building at 50 Mechanic Street.